

Aurora Power Systems APG-500

Standby Diesel Generator · Technical Datasheet

Rated Output	500 kVA / 400 kW @ 0.8 PF
Voltage / Frequency	400V 3-phase, 50 Hz
Prime Mover	6-cylinder turbocharged diesel, water-cooled
Starting System	24V DC electric start
Fuel Tank (base)	400 L integral base tank
Cooling	Radiator, engine-driven fan

The APG-500 is designed for standby/emergency duty in facilities requiring automatic mains-failure changeover. Typical installation pairs two units for alternating weekly duty against a single facility load, each unit individually rated for the full load.

Dimensions & Weight

Length	3400 mm
Width	1200 mm
Height	1850 mm
Dry Weight	3950 kg

Warranty and Service

Aurora Power Systems warrants the APG-500 for 24 months from commissioning date or 2000 running hours, whichever occurs first. Scheduled maintenance intervals are documented in the facility's own equipment manual for the installed unit.